





Agenda - 27 September 2017


Attachment 3.1.3











-SEMI TRAILER

TURN AROUND AREA.

-BIO SECURITY

GATE AND

WHEEL WASH.

EXTRACTION

FANS. OUTER

COOLING PADS.

BOTH SIDES OF

BROILER SHED.

(8.5mx3.4 Ø APPROX)

4 No. X FEEU

— SEDIMENTATION POND.

REFER TO TYPICAL

SECTION ON SHEET FO2.

\$ILOS. (8.5mx3.40)

135 FORRESTERS RD

WOOREEN 3953

DEVELOPMENT PLAN

SCALE 1:4000H AT A1 SIZE 1:8000H AT A3 SIZE 100m

END ONLY (TYP)

125 PITT RD

HALLSTON 3953

VISITOR PARKING. —

PER PLANNING

REQUIREMENTS.

20mx8m MACHINERY SHED, -

INCL, OFFICE, FREEZER AND

UPPER CUTOFF-

DRAINS.

STORAGE TANK

2 MEGA LITRE WATER

STORAGE TANKS

WHEEL WASH.

945 LEONGATHA-YARRAGON RD

2.0m WIDE x 30m — LONG PASSING LANE

20 MEGA LITRE (MIN.) STORAGE DAM FOR -OPERATIONAL DRAINAGE TREATMENT

-LANDSCAPE BUFFER

STRIP. REFER TO LANDSCAPE PLANS

AND REUSE. SEDIMENTATION POND (PROVISION FOR 28.3MLs SUBJECT TO DESIGN INTENT. REFER TO TYPICAL

SECTIONS ON SHEET F02.

870 LEONGATHA-YARRAGON RD

WOOREEN 3953

HALLSTON 3953



FOR AND AT ALL TIMES PROVIDE A SAFE WORKING AND SAFETY REGULATIONS. IN ACCORDANCE WITH CLAUSE 15 OF AS2124-1992, CONTRACTOR'S EMPLOYEES AND ALL OTHER PEOPLE WHO ARE ON OR ADJACENT TO THE SITE. THE CONTRACTOR MUST COMPLY WITH THE VICTORIAN

BORING NEAR OR ACROSS EXISTING SERVICES.

THE CONTRACTOR SHALL BE TOTALLY RESPONSIBLE ENVIRONMENT IN THE VICINITY OF THE SITE OF WORKS IN FULL COMPLIANCE WITH THE OCCUPATIONAL HEALTH THE CONTRACTOR MUST ENSURE THE SAFETY OF THE

1) DAM CAPACITY INCLUDES 10 ML FOR OPERATIONAL STORAGE AND 4ML FOR 10 YEAR ARI ONSITE DETENTION

- Denotes Broiler Shed Cooling Pads

- Denotes Existing Residence

- Denotes Watercourse

- Denotes Gully

- Denotes 686m Radius from approx. centres of existing Dwellings

- Denotes Access Road (5.0m wide unsealed)

- Denotes Open Earth swales to direct operational catchment to dam


- Denotes Upper Open Earth cutoff drain

- Denotes Extraction Fans

- Denotes Feeding Silos


- Denotes Gas Tanks

DESIGN STAGE.











SEMI TRAILER TRUCK



MINOR LOADING DOCK



CLIENT COMMENTS ADDED LOT BOUNDARY, NOTES & PASSING AREA UPDATED AO UPDATED TO COUNCIL COMMENTS LOT BOUNDARIES UPDATED PRELIMINARY ISSUE PRELIMINARY ISSUE Des. Chk. Appr. Date

PRELIMINARY

CHICKEN FARMS AUSTRALIA PTY LTD

PROPOSED BROILER FARM 80 PITT ROAD, WOOREEN

F 01

DEVELOPMENT PLAN





and a reduction in carbon emissions. We endorse the use of recycled products and encourage the contractor to utilise recycled products where a comparable, approved alternative to raw quarry products exists.

Scale: AS SHOWN @ A1 Municipality: SOUTH GIPPSLAND Melway Ref. -

Planners Surveyors Engineers Building 2 3 Ordish Road, Dandenong South, Victoria 3175 Tel: 03 97941600 - Fax: 03 97949532 E-mail: manager@klms.com.au

AND DEVELOPMENT INTELLIGENCE Web: www.klmspatial.com.au

DETAIL DESIGN.

*

ARM ENTRANCE. — REFER TRAFFIC ENGINEERS DESIGN.

LEONGA THA

5.0m WIDE-ACCESS ROAD

THIS PLAN HAS BEEN PREPARED TO REPRESENT TYPICAL

APPROVAL. ALL DETAILS ARE SUBJECT TO REFINEMENT DURING

ENGINEERING DETAILS FOR THE PURPOSE OF PLANNING

---- - Denotes 200m Buffer from Watercourse - Denotes 5m AHD Contour Interval - Denotes Chicken Shed (135m long x 17.4m wide)

OCCUPATIONAL HEALTH AND SAFETY ACT 2004, INCLUDING SAFETY HELMETS, SAFETY BOOTS, EAR AND EYE PROTECTION, WHERE APPROPRIATE.

NOTES


LEGEND

- 2) EARTHWORKS SUBJECT TO REFINEMENT AT DETAIL

VEHICLE TURNING MOVEMENTS







EARTHWORKS SUMMARY


| ı | CHICKEN SHEDS AND ACCESS | RUADS |
|---|--------------------------|---------------------|
| | ESTIMATED VOLUME CUT: | -59,993.25 |
| | ESTIMATED VOLUME FILL | 72,786.45 |
| | DEFICIT: | <u>12,793.00г</u> |
| | ONSITE STORAGE DAMS | |
| | ESTIMATED VOLUME CUT: | -15,934.20n |
| | ESTIMATED VOLUME FILL | 7,246.04п |
| | DEFICIT: | - <u>8,688.15</u> m |
| | ENTRANCE ACCESS ROAD | |

ESTIMATED VOLUME CUT: -25801.611m³ ESTIMATED VOLUME FILL 47427.487m³ 21,625.875m³

REFER TO GENRAL NOTE (2)

KLM Spatial and the developer of this project support the use of sustainable civil products,





To Later Detail


PLANT SCHEDULE

Refer to Plant Schedule

| SYM | BOTANICAL NAME | COMMONNAME | D/E N/Ex* | HEIGHT X WIDTH AT MATURITY | MIN SUPPLY SIZE | IN TIAL QTY | TARGET QTY |
|-------|-------------------------|-------------------------|-----------|----------------------------|--------------------|-------------|------------|
| TREES | | | | | | | |
| Am | Acacia melanoxylon | Blackw ood | E/N | 12-20 x 8m | 50mm tube | 295 | 118 |
| Ec | Eucalyptus cypellocarpa | Mountain Grey Gum | E/N | 4-10 x 5m | 50mm tube | 315 | 126 |
| Er | Eucalyptus radiata | Narrow -leaf Peppermint | E/N | 10-40 x 14m | 50mm tube | 360 | 144 |
| Ev | Eucalyptus viminalis | Manna Gum | E/N | 10-50 x 11m | 50mm tube | 280 | 112 |
| Ss | Syzygium smithii | Standard Lilly Pilly | E/N | 8-10 x 6m | 50mm tube | 315 | 126 |
| | | | | | TOTAL | 1565 | 626 |

after planting.

All plant species selected from Strzelecki Flain Bioregion EVC 16, 29, 30 and 32 of the Department of Sustainability and Environment. Allow ance for 40% planting success rate. *D/E = Deciduous/Evergreen N/Ex = Native/Exotic



Place plants in position according to densities required and prepare planting holes, with as minimal soil disturbance as possible, to a minimum size of 150mm deep x 200mm in diameter. Plants shall be thoroughly soaked via immersion in water prior to planting. If the site soil is very dry then planting holes are also to be filled with water and allowed to drain Place plant in hole so that top of soil level in pot matches surrounding soil level. Back fill with existing site topsoil,

removing any debris limiting to plant growth. Provide weed

matting or mulch area as specified taking care to keep mulch

clear of plant stem. All plants are to be thoroughly watered

D1 TYPICAL TUBE PLANTING DETAIL

SPECIFICATION NOTES

and weed control

procedure 1. Pre-planting Preparation

Revegetation works to follow a three part

 Herbicide treatment to the revegetation site area, including general clean-up of site area. Ripping of area to 400mm-1000mm with suitable

equipment in maximum 3m by 6m hash pattern to cover entire revegetation area. 2. Planting of tubestock into rip lines of prepared area 3. Post Vegetation Establishment maintenance/irrigation

Pre-planting Preparation Herbicide treatment to entire planting area to remove all

vegetation to area to be revegetated. All weeds shall be thoroughly removed. All vegetative material, including roots and rhizomes of non-woody perennials and woody suckering weeds, is to be removed or appropriately controlled using chemical means. The stumps of non-suckering woody perennials are to be stump ground. All vegetative material shall be appropriately disposed of offsite in a manner which will not allow their re-establishment

elsewhere. Any chemical controls are to be used in

accordance with manufacturer's instructions and standard

If any existing planting is to be retained then care must be

occupational health and safety procedures.

taken to ensure these are not damaged during weed removal. This also implies that any herbicides used are suitable for use around the vegetation to be retained. ripper as deep as possible (min. 400mm, 1000mm preferred) to ensure good shattering of subsoil and subsequent root and

moisture penetration. Ripping to be completed with suitable equipment in maximum 3m by 6m hash pattern to cover entire revegetation area. Late winter Early Spring: Contact herbicide spray treatment along the rip lines with a suitable spray in accordance with the manufacturer's specification. Spray along the rip lines

with a second application of weed spray in accordance with

the manufacturer's specification. (If required)

and allowed to drain completely.

Planting Planting will take place in two separate stages. The first stage of planting will be for trees only. One year later the second stage of planting for shrubs an groundcovers will take place. Rotary hoe all rip line(s) and soil mounds with tractor to level surface, for appropriate planting bed. Planting shall be carried out using accepted horticultural practices with all plants conforming to the species, size and quantities indicated on the Landscape Plan and Plant Schedule. Plants shall be thoroughly soaked through immersion in water prior to planting and if the planting soil is very dry then the planting hole is also to be filled with water

All plants shall be appropriately hardened off in the nursery. Plant Establishment Period restriction or damage, vigorous, well established, and free species or variety, hardened off - not soft or forced. Plants that do not meet these requirements will be rejected All tubestock and seed for planting is to be of local

provenance and suitable to site. If conditions are very cold

and wet, wait for warmer weather. Tubestock: Plant tubestock at suggested centres based on species (refer drawings). Tubestock are to be planted 100-200mm away from the rip lines. Planting hole dug no deeper than the height of the roots, and hole filled only to the base of the plant crow Refer detail. Planting guards are to be placed and bamboo staked around every individual plant (rabbit protection and sheltered environment for plant growth).

Biodegradable Weed Mats made from Recycled Fibre with dimensions 370mm x 370mm, to be fitted to the base of each plant (tree, shrub, ground cover). Weeds should be cleared from area prior to installation around plant base. Fasten Weed Mat with cardboard guard and bamboo stakes. Refer

Post Vegetation Establishment

Addition of organic mulch is to be supplied to all plant bases and is to be of chipped or shredded vegetable material with 80% of particles in the size range 25 to 50mm in plan and 5 **Deep ripping:** Deep rip along planting lines with a single-tine to 10mm in thickness. No particles are to exceed 75mm in plan. Mulch shall be free of deleterious and extraneous matter such as soil, weeds and sticks. Mulch is to be stockpiled and thoroughly weathered prior to delivery.

> This mulch shall be laid to a minimum depth of 50mm and is to be sloped towards plant stems and kept 100mm back from the stems of all plants to prevent collar rot.

Weed management is critical with vegetation establishment. Strategies are as follows: Mulch is to be added as necessary to keep weeds to manageable levels. Exhaust the soil seed bank by removing weeds and/or spot spray with herbicide.

planting/guarding. Minimise disturbance of soils to establish canopy and groundcover and avoid excess weed germination. Establish a native grass species as a ground cover as Coppice established vegetation to create canopy at

ground level to provide intermediate cover.

Use of weed mats around stock, during

Use plants with the following characteristics: Large healthy Maintenance and Establishment means the care and root systems with no evidence of root curl or pot bound maintenance of the revegetation area by accepted horticultural practices, as well as rectifying any defects that from disease and pests and of good form, consistent with the become apparent in the work under normal use. This plant establishment and maintenance period will last for 2 years after initial works take place. This shall include, but shall not be limited to watering, fertilising, weeding, pruning, pest and disease control, cultivation, re-staking and replacement of any plants that fail or are damaged with plants of the same species and size. This is to the onus of the owner.

> Recommend supplemental water to be supplied to all newly planted plants, particularly during hot weather. Allow for approximately 10mm per meter squared of planting area to be delivered to the soil surface around each plant. Water delivery is more critical during the first two years of plant

Failed Plant Material and Replacement Addition of species underrepresented or failed within the community are to be replaced with more suitable

visual form is to be completed by an experienced revegetation manager. The revegetation area must function and appear as a 'natural' vegetation area.


An appropriate native grass seed (eg. Microlaena stipoides -

Maintenance and achieving the appropriate structural

Weeping Grass or similar mix) is to be sown as lawn. Thoroughly eradicate weeds prior to the installation of lawn seed. This is to be done by approved methods such as manual removal, non-residual systemic or knock-down

Topsoil is to be moistened to its full depth prior to the application of seed. Seed is to be sowed 10-15 mm below the soil surface. Germination may take from 10-14 days in spring or summer or considerably longer in cooler conditions. Sowing rate: 1kg/100m² and spread in a manner that achieves even distribution. Lawn is to be irrigated immediately following sowing, either by hand or through an irrigation system, and is to continue to be irrigated until grass is fully established.

Any areas of lawn which have failed to germinate (achieve an evenly green 95% covering of a consistent height) are to be re-seeded within one month of original sowing date.





JOHN PATRICK LANDSCAPE ARCHITECTS PTY LTD A Revised Site Layout 324 Victoria Street, Richmond, VIC 3121 T +61 3 9429 4855

F +61 3 9429 8211

admin@johnpatrick.com.au

www.johnpatrick.com.au

30.01.2017 LR This drawing must not be copied in whole or in part without the consent of John Patrick Landscape Architects Pty Ltd Do not scale off drawings NOT FOR CONSTRUCTION

DATE BY

CHICKEN FARMS AUSTRALIA

80 PIT ROAD, WOOREEN

PROJECT

DRAWING Landscape Plan for Town Planning PROPOSED BROILER FARM

SCALE 1:1000 @ A0 DECEMBER 2016 CHECKED JOB NO DWG NO CAD FILE 16-981-L-TP01-REV-A